

Leg	gend
•	Iron pipe or pin found
	Calculated point
	Proposed property line
	Approximate property line
ohu	Existing utility pole/overhead line
	Existing easement
	Existing Wetland (delineation by Gilman & Briggs Environmental, see note 3)
В	Existing 50ft wetland buffer
·	Existing stonewall
	Edge of woods/cluster
 _	Drainage
—— FM — — — — — —	New Sewer Forcemain
— W— — — —	New Water Service
	Proposed building setbacks
	Proposed 60' Right of Way
	Proposed Wastewater Easement Area



B-1





Notes:

- 1. This plan is not a boundary survey. Portion of parcel was depicted in administrative subdivision prepared by Krebs and Lansing Consulting Engineers Inc. and recorded in the Richmond land records. Remaining parcel outline references tax map downloaded from VCGI and physical evidence observed in the field.
- 2. Topographic information shown on plan was developed by Krebs and Lansing Consulting Engineers Inc. Topographical survey completed in 2019, 2020, and 2021.
- 3. Wetlands delineation shown on plan was completed by Gilman and Briggs Environmental on November 5, 2019. The areas delineated were characterized as Class II wetland according to the Vermont Wetland Rules last revised April 1, 2017. The location of the wetland flags was completed by Krebs and Lansing Consulting Engineers Inc. on November 6, 2019 and December 16 & 17, 2019.
- 4. This plan may be copied to the extent necessary to comply with Vermont State Laws pertaining to accessibility to public records. Use of these plans for construction purposes requires the permission of Krebs & Lansing Consulting Engineers.
- 5. Large animal habitat, imagery, and LIDAR information downloaded from the Vermont Center for Geographic Information (VCGI).

Leg	gend
_! <u>2</u>	Survey control point
TP-3	Soil test hole
\bigcirc	Utility pole
ohu	Overhead utility line
	Temporary bench mark
	Approximate property line
	Proposed property line
	Edge of woods/cluster
	Drainage











The location of the septic tank // and pump station are shown for illustrative purposes. The exact location will be determined when the house is sited. The tanks shall maintain a minimum of 50' separation from the drilled well, and 10' separation from the building foundation. (typical)

Install new precast concrete 5 outlet distribution box with flow levelers and riser to ground surface with insulation. Backfill distribution box with 1ft minimum cover, slope ground away from wastewater trench.

TP - 23

TP-22 . HSWT@ >60"

694.[38

HSW 60"

31684 × 697.66

TP-18

31686 : 696.4 q

8 31688 × 692.74

HSW(T@ >

TP-13∖

 \bigcirc

HSWT@ 84"

For the length of the driveway, the driveway grade shall not exceed twelve (12) percent except that the last 200 feet from the foundation of the primary structure being served shall not exceed fifteen (15) percent. In measuring the compliance of a driveway, the maximum grade may not be exceeded along the driveway

> Proposed 12ft wide gravel driveway to

New 18" ADS culvert







<section-header><section-header><section-header><section-header><text></text></section-header></section-header></section-header></section-header>
KREBS & KREBS & LANSING CONSULTING ENGINEERS164 Main Street, Suite 201 Colchester, Vermont 05446P: (802) 878-0375 www.krebsandlansing.com
STAMP:
$0' \qquad 30' \qquad 60' \qquad 90'$ $\underline{Bar Scale} \qquad 1'' = 30'$
Project: Randall Farm 6 Lot Subdivision Peggy M. Farr Revocable Trust
Project No.19327Scaleas notedDrawn byJAR/SWHChecked by
Revisions No. Date Description
Drawing Title Lot 4 Driveway Profile
Drawing No. C-5.1

6+50



Basis of Design for System A <u>Primary Shallow In-Ground Trench Sty</u>le Lot 3 – "System A" for a 4 Bedroom SFR 490 GPD Shallow Design Flow: In-Ground Trench Style Primary - 1 single family houses (4 bedroom) = 490 G.P.D. ;Wastewater System. Use (2) 4' wide ____ – For a 4 Bedroom Single Family – Design Flow = 3 bedrooms 140gpd * 3 gals/day/bedrooom = 420 gals/day 76.5' long with 6" of Stone - Additional bedroom based on 1 person per/bedroom $_{+}$ = 70 gpd Underneath Distribution Pipe Total Design Flow 490 gpd Application Rate: For Shallow In Ground Style Trench Use bed application rate = Q = .80Table 9-3 (Loamy fine sand / SG) Required Leach Area for Primary: - Area required = $\frac{490 \text{ GPD}}{8}$ = 612.5 s.f. - Use 4' shallow in ground - Required bed length = $\frac{612.5 \text{ s. f.}}{4 \text{ ft}}$ = 153.12 ft. Use 2, 4' width x 76.5' shallow in ground trench style wastewater systems with 6" crushed stone under distribution pipe for Primary wastewater system Septic Tank: – Use 1000 gallon, 2 compartment precast concrete septic tank with outlet filter and risers to ground surface Pump Station: – Use 1000 gallon simplex pump station - dose = 122.5 gal, Emergency Storage Alarm = 490 gal Lot 3 New Replacement /HSW7@ 36" Basis of Design for "System A" Replacement TP-11 At-Grade Wastewater Pretreated Effluent At-Grade System HŚWT@/30" Disposal System. Use (2) 6' effective width x 51.5' Design Flow: long bed. See table for -1 single family houses (4 bedroom) = 490 G.P.D. elevations. - For a 4 Bedroom Single Family - Design Flow = 3 bedrooms 140gpd * 3 gals/day/bedrooom = 420 gals/day - Additional bedroom based on 1 person per/bedroom $_{+}$ = 70 gpd Total Design Flow = 490 apd Application Rate: For At Grade Application Rate Lot 2 – "System B" for a 4 Use application rate = Q = .8Table 1. Linear Loading Rate F Bedroom SFR 490 GPD Table 9-3 (Loamy fine sand / SG) Pretreated mound style Required Leach Area for replacement: wastewater system 5' x 49' - Area required = $\frac{490 \text{ GPD}}{8}$ = 612.5 s.f. Soil Texture with 12" of sand underneath Coarse sand, Sand, I Loamy Sand - Use 6' effective at grade stone. Coarse Sandy Loam, - Required effective length = $\frac{612.5 \text{ s. f.}}{6 \text{ ft}}$ = 102.08 ft. Fine Sand, Loamy Fir Fine Sandy Loam, Ve Use 2, 6' effective width x 51.5' At-grade wastewater systems for replacement wastewater system with pretreated effluent Silt Loam Sandy Clay Loam, Sil Septic Tank: Sandy Clay, Silty Clay – Use 1000 gallon, 2 compartment precast concrete septic tank with outlet filter and risers to ground surface **B** Series Pump Station & Pretreatment: Department of Environmental Conser – Use 1000 gallon simplex pump station Wetland - dose = 122.5 gal, Emergency Storage Alarm = 490 gal B1-B10 - Pretreatment unit to treat 490 gallons per day of effluent. Proposed wastewater system area easement for Basis of Design for "System B & C" Mound the benefit of Lot 1 & Lot 2 for installation, Style Wastewater Disposal System maintenance and access. Design Flow: - For an Proposed 4 Bedroom Single Family - Design Flow = 3 bedrooms 140gpd * 3 gals/day/bedrooom = 420 gals/day - Additional bedroom based on 1 person per/bedroom = 70 gpd Total Design Flow = 490 gpd Application Rate: – For mound system - Application rate = Q = 1.0 gals/s.f./day – For filtrate effluent disposal system Large - Application rate = 2 * Q = 2 * 1.0 = 2.0 gals/s.f./day animal habitat line Required Leach Area: downloaded - Area required = $\frac{490}{20}$ = 245 s.f. from VCGI – Use 5' wide Bed - Required system length = $\frac{245 \text{ s. f.}}{5 \text{ ft.}}$ = 49.0 ft. -Use 1, 49' long x 5' wide bed style mound Septic Tank & Pump Station/Pretreatment: - New 1,000 gallon septic tank with outlet filter and risers to ground surface - New 1,000 gallon, precast concrete pump station with simplex pump, audible alarm and riser to ground surface - Pretreatment unit to treat 490 gallons per day of effluent. Not<u>es:</u> 1. This plan is not a boundary survey. Portion of parcel was depicted in adm Krebs and Lansing Consulting Engineers Inc. and recorded in the Richmond outline references tax map downloaded from VCGI and physical evidence obs 2. Topographic information shown on plan was developed by Krebs and Lansing Topographical survey completed in 2019, 2020, and 2021. 3. Wetlands delineation shown on plan was completed by Gilman and Briggs En The areas delineated were characterized as Class II wetland according to the revised April 1, 2017. The location of the wetland flags was completed by Kr Engineers Inc. on November 6, 2019 and December 16 & 17, 2019. 4. This plan may be copied to the extent necessary to comply with Vermont accessibility to public records. Use of these plans for construction purposes & Lansing Consulting Engineers.

5. Large animal habitat, imagery, and LIDAR information downloaded from the Information (VCGI).

Performance Based Mounding Analysis for Mounds Systems B & C

For Primary System Design Flow = 490 gpd Natural Ground Slope = 15–20% (Average) Receiving Soil Texture = Fine loamy sand
From Table 1: Linear Loading Rate Factor (f) = 33.7 From Soil Test Logs: Seasonal High Water Table at 16 inches 16"- 6" reserved unsaturated soil for assumed induced mounding, (H) = 10"/ 12' = .83' (based on Test Pits)
Primary Linear Loading Rate: (LLR) LLR = (h) * (f) LLR = (.83) * (33.7) = (27.97) LLR = 27.97 gpd/lf
Primary System Length: (L)
For a Design Flow Q = 490 gpd

Randall

Farm

Subdivison

19327/dwas/SP-Earr.dwa

LL LL Prin Fi L	R = (. R = 2 nary S or a D = 490	283) * (27.97 gpc System Pesign Flo 9 gpd /	33.7) = d/lf Lengt bw Q = 27.97 g	(27.97) h: (L) 490 gp apd/lf	7)) Dd				R	East Hill Road	d nont
L 43	= 17.3 9 lineai	52 (minir r feet pr	num ler ovided	ngth red	quired)			164 Col	4 Main Street, Su Ichester, Vermor	KREBS LANSI consulting ht 05446 P: (802) www.kre	S & NG ENGINEERS 878-0375 bsandlansing.com
										RENSHAW	and
acto	ors Bo	used on	Soil T	exture						I	
			G RATE F	ACTORS	5 (f)						
	Natura 0-2%	I Ground 2.1-4%	Slope 4.1-6%	6.1-8%	8.1-10	% 10.1-15	% 15.1-20%				
	7.5	22.4	37.4	52.4	52.4	52.4	52.4				
Very	3.7	11.2	18.7	26.2	33.7	33.7	33.7				
	1.5	4.4	7.5	10.5	13.5	18.7	26.2			Verm Grid	
	0.7	2.2	3.7	7.9 5.2	6.7	9.4	13.1			ont Sto North	
	0.4	0.7	1.1	1.6	2.0	2.8	3.9			nte Plai (NAD83	
e of vatic	Vermo on, Was	ont Agenc atewater (<u>CCGCN</u>	sy of Na Managen P d Surve,	y contr	esources vision. —			(0' 	30' 60 Scale 1"	0' 90'
			Soil te	est hol	е				Project:		
-e	TBM #1		Tempo	prary b	ench m	ark		1	P a	ndall Fa	rm
	- —140 —		Finish	Conto	ur				Na	110a111'c	••••
			Overh	ead Pc	wer				6 L01	t Subdiv	/1S10n
<i>15</i>			- Existi - Evicti	ng Con Ing Uno	tour Ioraroun	d Power			Peg	gy M. F	Farr
 	<u> </u>	Ç ₩ * S	New V Survey	Vater L V Contr	ine/Hyd ol Point	lrant/Val	ve/Shutoff		Revo	ocable T	Trust
			Appro.	ximate	Propert	ty Line		Р	roject No.	19327	
			Potabl Dispos	e Water al Isola	- Supply, tion Env	/ Wastew elope	oter	s	cale	1"=30'	
-			Propos	sed Eas	sement	/		D	rawn by	JAR/SV	VH
								С	hecked by	y	
								D	Date	03/19/2	021
								R	levisions		
								Ν	lo. Date	Description	
								-			
								_			
								_			
ninis 1 Ior	trative	subdivis	sion pre	pared l	by			D	Prawing Tit	le	
g Co	ed in t onsultir	the field. ng Engin	eers Ind	c.	.,				Waste	ewater D Ian Lots)isposal 1-3
nvira e Ve (reh	onment ermont s and	tal on No Wetland Lansing	ovembei 1 Rules Consuli	r 5, 20 Tast tina	019.				•		
State Laws pertaining to State state state permission of Krebs						D	Drawing No.). ~ 7 ($\mathbf{\cap}$		
s rec	quires										

and Natural G

	Natural	Ground	Slope				
	0-2%	2.1-4%	4.1-6%	6.1-8%	8.1-10%	10.1–15%	15.1-20%
.oamy Coarse Sand,	7.5	22.4	37.4	52.4	52.4	52.4	52.4
Sandy Loam, Fine Sand, Very le Sand, Loamy Very Fine	3.7	11.2	18.7	26.2	33.7	33.7	33.7
ry Fine Sandy Loam	1.5	4.4	7.5	10.5	13.5	18.7	26.2
	1.1	3.4	5.6	7.9	10.1	14.0	19.6
	0.7	2.2	3.7	5.2	6.7	9.4	13.1
ty Clay Loam, Clay Loam	0.4	1.1	1.9	2.6	3.4	4.7	6.5
/ Clav	0.2	0.7	1.1	1.6	2.0	2.8	3.9

Table from "Simplified Procedure for February 6, 2003, published by State





Install new precast concrete 5 outlet distribution box with flow levelers and riser to ground surface with insulation. Backfill distribution box with 1ft minimum cover, slope ground away from wastewater trench.

The location of the septic tank // and pump station are shown for illustrative purposes. The exact location will be determined when the house is sited. The tanks shall maintain a minimum of 50' separation from the drilled well, and 10' separation from the building foundation. (typical)

SWT@ 75"

TP-1

 \bigcirc

HSWT@ 67"

TP-7

TP-8

HSWT@ 24"

HS₩T@ 44"

HSWT@ 78'

TP-6

_HSWI@ 70"

HSWT@(24"

For the length of the driveway, the driveway grade shall not exceed twelve (12) percent except that the last 200 feet from the foundation of the primary structure being served shall not exceed fifteen (15) percent. In measuring the compliance of a driveway, the maximum grade may not be exceeded along the driveway center-line.

1. This plan is not a boundary survey. Portion of parcel was depicted in administrative subdivision prepared by Krebs and Lansing Consulting Engineers Inc. and recorded in the Richmond land records. Remaining parcel

3. Wetlands delineation shown on plan was completed by Gilman and Briggs Environmental on November 5, 2019. The areas delineated were characterized as Class II wetland according to the Vermont Wetland Rules last revised April 1, 2017. The location of the wetland flags was completed by Krebs and Lansing Consulting

accessibility to public records. Use of these plans for construction purposes requires the permission of Krebs

<u>Basis of Design – Onsite Potable Water System Lots 4 & 5</u> Average Day Demand = 4 bedrooms (3 * 140 GPD x 3 bedrooms + 70 GPD per add'i bedroom) = 490 GPD + 1 bedroom accessory apartment (1 * 140 GPD x 1 bedroom) = 140 GPD Total Average Day Demand = 630 Gallons Per Day Maximum Day Demand <u>630 G.P.</u>D. = .88 G.P.M. 720 min./perday Instantaneous Peak Demand = 5 GPM/Unit = 10 G.P.M. Source capacity = Not required for projects with maximum day demand under 2 GPM or less Storage capacity = To be calculated after well drillers yield test completed Minimum pump Capacity = 10 G.P.M.

Operating pressure range 40 psi to 60 psi The well is not located in a flood plain

Design Flow:

Application Rate: For In Ground Style Trench Use bed application rate = Q = .80Table 9-3 (Loamy fine sand / SG)

Required Leach Area for Primary: $- Area required = \frac{630 GPD}{8} = 787.5 s.f.$

Septic Tank: Pump Station:

(Contact Engineer Drilled well serving Drilled well serving Lake and pond impo River, streams Drainage swales, roa Main or municipal w Service water lines Roadways, driveways Top of embankmen Property line Other disposal field Foundation, footing Suction water line <u>Note:</u>

_ _ _ _

_____ ohp –



Boulder

Boulder

Basis of Design for Lots 4 & 5 Primary & Replacement In-Ground Trench Style Wastewater System

- For a new 4 bedroom residence & 1 bedroom ADU – Design Flow = 3 bedrooms * 140 gals/day/bedroom + 1 bedroom @ 70 gpd + 1 bedroom accessory apartment * 140 gals/day/bedroom Total Design Flow = 420 gals/day + 70 gals/day + 140 gals/day = 630 gals/day

– Use 4' in ground trench - Required bed length = $\frac{787.5 \text{ s.f.}}{4 \text{ ft}}$ = 196.87 ft. – Use 3, 4' width x 66' in ground trench style wastewater systems with 12" crushed stone under distribution pipe for Primary wastewater system

- Use 1000 gallon, 2 compartment precast concrete septic tank with outlet filter and risers to ground surface

- Use 1000 gallon simplex pump station - dose = 122.5 gal, Emergency Storage Alarm = 490 gal

Minimum Isolation Distances

or any Clarifications or conflicts)	Edge of System	Septic Tank	Sewer
1 home - un slope of system	100	50	50
1 home - down slope of system	200	50	50
oundment — standing water	50	25	25
Sunanient Standing Water	50	25	10
adway ditches	25	_	_
vater lines	50	50	10
	25	25	10
s, parking lots	10 (25 downslope)	5	_
' or slope > 30%	25	10	_
	25	10	10
	10	10	10
or replacement area	10	_	_
drains, curtain drains	35 (75 downslope)	10	_
	100	50	50

Horizontal Distance (ft.)

These distances may be increased if necessary to provide adequate protection.

	Legen	d
	<u> 24</u>	Survey control point
		Soil test hole
		Temporary bench mark
		Finish Contour
ohp		Overhead Power
	150 —	Existing Contour
——— ugp	· · ·	Existing Underground Power
— w —	\chi	New Water Line/Hydrant/Valve/Shutoff
		Survey Control Point
		Approximate Property Line
		Potable Water Supply/ Wastewater Disposal Isolation Envelope
		Proposed Easement





19327/dwas/SP-Earr.dwa





WETLAND PLANTING SOIL CHARACTERISTICS

Parameter	Value
pH range	6.0 to 7.0
Organic matter	3% comprised of composted leaf mulch
Magnesium	35 lbs per acre, minimum
Phosphorus (P205)	10-30 mg/kg utilizing Mehlich-3 or Modified Morgan test
Potassium (K20)	85 lbs per acre, minimum
Soluble salts	500 ppm, maximum
Soil (low hydraulic conductivity (0.1-0.01 ft/day)	
Sieve Size	Percent Passing
No. 16	100%
No. 40	85-100%
No. 60	40-60%
No. 200 (Clay content < 15%)	5-10%

A dense and vigorous vegetative cover must be established and maintained over all pervious drainage areas upslope of the system





Install cap on top of pipe at water surface elevation Drill small diameter orifice in top

The Vermont Stormwater Management Manual

- 1'-0" - WELD (TYP.) 2" x 1/4" STEEL STOCK ALL AROUND conform frame to shape of concrete structure. 1/2" DIAMETER HOLES @24" O/C MAX. (TYP.) 5 3 lb/ft^2 expanded aluminum fabric on top, bottom and sides. WELD 1"x1"x1/8" ANGLE OVER ALL EDGES (TYP.) Provide Shop Drawing to 1'-5" Engineer for approval. NOTES FOR TRASH RACK 1. TRASH RACK TO BE CENTERED OVER OPENING. 2. STEEL TO CONFORM TO ASTM A-36. 3. ALL SURFACES TO BE COATED WITH ZRC COLD GALVANIZING COMPOUND AFTER WELDING.

Appendix D5

4. TRASH RACK TO BE FASTENED TO THE WALL WITH 1/2" MASONRY ANCHORS. TRASH RACK TO BE REMOVABLE.

Figure D.1. Trash Rack Protection for Low Flow Orifice

Trash Rack Detail N. T.S.

172

Randall Farm
Subdivison
East Hill Road Richmond, Vermont
KREBS & KREBS & Consulting Engineers 164 Main Street, Suite 201 Colchester, Vermont 05446 P: (802) 878-0375 www.krebsandlansing.com
STAMP:
Randall Farm 6 Lot Subdivision Peggy M. Farr Revocable Trust
Project No. 19327 Scale N.T.S. Drawn by JAR/SWH Checked by
Revisions No. Date Description
Drawing Title Stomrwater Details
Drawing No.

EROSION PREVENTION & SEDIMENT CONTROL NOTES:

- 1. The limit of disturbance shall be clearly defined by the Contractors survey prior to clearing. All sediment control measures must be installed ahead of initiating principal earthwork activities for the project.
- 2. All erosion controls shall be installed as detailed in the publication Vermont Standards and Specifications for Erosion Prevention & Sediment Control and in accordance with these project plans.

The site shall then be cleared and grubbed. All roots, stumps and deleterious materials shall be removed from the site. The Contractor shall minimize the amount of disturbed land at any given time.

- 3. All erosion control shall be placed as shown on the drawings or as ordered by the Engineer. The Contractor shall maintain the erosion control measures until the Engineer is satisfied that permanent ground cover is established and that further measures are not required. It shall be the responsibility of the Contractor to employ appropriate erosion control as shown on these drawings and any other measures as necessary to trap sediment on site.
- 4. All areas of disturbance must have temporary or final stabilization within 14 days of initial disturbance. After this time any disturbance in the area must be stabilized at the end of each work day. The following exceptions apply: i) Stabilization is not required if work is to continue in the area within 24 hours and there is no precipitation forecast for the next 24 hours. ii) Stabilization is not required if the work is occurring in a self-contained excavation (i.e. no outlet) with a depth of 2 feet or greater (e.g. house foundation excavation, utility trenches).
- 5. Contractor shall be responsible for all erosion control measures necessary to comply with the approved Erosion & Sediment Control Plan for this project. This plan indicates specific erosion control measures that must be installed to stabilize specific locations of the site. All necessary erosion control measures needed to minimize the discharge of sediment from site are not necessarily shown on the drawing.







- A MACHINE-PRODUCED MAT OF 100% AGRICULTURAL STRAW.
- DISTRIBUTED OVER THE ENTIRE AREA OF THE MAT. THE BLANKET SHALL BE COVERED ON THE TOP SIDE WITH 100% BIODEGRADABLE WOVEN NATURAL ORGANIC FIBER NETTING HAVING AN APPROXIMATE 1/2" X 1" MESH AND BE SEWN TOGETHER WITH **BIODEGRADABLE THREAD.**
- NORTH AMERICAN GREEN, INC. (812-867-6632) OR EQUIVALENT. EROSION CONTROL BLANKET SHALL HAVE THE FOLLOWING PROPERTIES:

- SHALL BE S75BN AS MANUFACTURED BY



14649 HIGHWAY 41 NORTH, EVANSVILLE, INDIANA 47725 USA 1-800-772-2040 CANADA 1-800-448-2040 www.nagreen.com

7. IN HIGH FLOW CHANNEL APPLICATIONS, A STAPLE CHECK SLOT IS RECOMMENDED AT 30 TO 40 FOOT (9m-12m) INTERVALS. USE A DOUBLE ROW OF STAPLES STAGGERED 4" (10cm) APART AND 4" (10cm) ON CENTER OVER ENTIRE WIDTH OF THE CHANNEL.

8. THE TERMINAL END OF THE BLANKETS MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30cm) APART IN A 6" (15cm) DEEP X 6" (15cm) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.

CRITICAL POINTS

A. OVERLAPS AND SEAMS B. PROJECTED WATER LINE

CHANNEL BOTTOM/SIDE SLOPE VERTICES

HORIZONTAL STAPLE SPACING SHOULD BE ALTERED IF NECESSARY TO ALLOW STAPLES TO SECURE THE CRITICAL POINTS ALONG THE CHANNEL SURFACE.

** IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15 cm) MAY BE NECESSARY TO PROPERLY ANCHOR THE BLANKETS.

V