



Suzanne Mantegna <smantegna@richmondvt.gov>

DRB app in FHOD Richmond

Eric Adam Wood <wood.eadam@gmail.com>

Wed, Sep 30, 2020 at 11:27 AM

To: Suzanne Mantegna <smantegna@richmondvt.gov>

Hey Suzanne,

Thanks for forwarding the questions over. Both the porch and mud room are built on concrete footings.

The mud room is supported on the side away from the house by 8" round on 20"x20" foot. There are 4 pieces of #4 rebar and the beam is anchored to concrete with a Simpson connector. The mud room is insulated under the floor with spray foam and the area underneath is screened with lattice so as to not create an enclosed area.

The steps are set on 6" round with 3 pieces of #4 rebar on feet (I think they were 16"x16") and anchored with a wedge anchor. The stringers are metal and have holes for anchoring directly to concrete so no added connector was used.

If there is anything else let me know!

Thanks,
Eric Adam Wood
802-735-4702

Sent from my iPhone

On Sep 30, 2020, at 10:23, Suzanne Mantegna <smantegna@richmondvt.gov> wrote:

[Quoted text hidden]

[Quoted text hidden]

[Quoted text hidden]

[Quoted text hidden]

<image002.png>

[Quoted text hidden]