

1. *The Contractor is responsible for excavation of all organic fill required to construct the project as shown and detailed. Organic fill removal is required within this 2.7+/- acre parcel only.*
2. *See test hole information in bid package for location and depth of organic fill.*
3. *All organic fill shall be removed from under and 5' outside the limits of sidewalks, driveways, and roads with in the 2.7+/- acre parcel.*
4. *The Contractor shall excavate and remove only that portion of organic fill required to construct footings and foundation walls. Removal of organic fill under building slabs is not required.*
5. *All excavated organic fill shall be trucked to the Town of Richmond Peet Gravel Pit. See site location map in bid documents. The Contractor shall stockpile organic fill in two areas designated on plan in bid documents.*
6. *The Contractor is limited to using 6 (six) 14 yard trucks per day. Each truck may make as many round trips as possible from between 8 AM to 4 PM. There shall be no operation of the gravel pit on holidays observed by the State of Vermont.*
7. *The Contractor is responsible for erosion control as specified on sheet C6.*

