

Specifications:

- · Posts are Black Locust, all other timbers are White Pine.
- · Principle timber joints secured with White Oak pegs.
- Posts are 5.5"x5.5"; Girts are 4"x5"; Ties are 5.5"x5"; Plates are beveled 3"x4"; Ridge is 3"x3".
 - · Roof is rough sawn pine boards with channel drain roofing.
 - · Signboard 42"x32" of 3/4" tongue-in-groove eastern white cedar.

Installation:

- *Kiosk comes in three parts: roof assembly, signboard assembly, and posts
- •Purchase will include installation directions including exact center-to center measurements for excavation
 - · After digging holes, installation should take crew of 4 strong people about 1 hour
 - We strongly recommend burying 12" x 4' sonotubes in post locations
 - · Insert posts into tubes and backfill with clean crushed stone.
 - · Concrete footings are not necessary, and burying bottoms of posts in concrete is not recommended

Recommendation:

The Black Locust posts are the best all natural wood choice available from the Northeastern forest.

They should have a service life of many decades with an in ground installation. Regardless,
we strongly recommend:

• Following THVT's best installation practices described on the website and in the installation directions
•Annual inspection of the post bases to ensure safe post condition, especially after the first decade of service.

Options:

THVT's Classic Kiosks have a range of possible roof and signboard customizations as well as possible addons. Please consult our website.

If needed, THVT can supply steel post bottom brackets. Please inquire for details.

For photos and more information, visit our website: www.timberhomesllc.com/kiosks

Prices are for pickup in Montpelier or Vershire, Vermont. Delivery quotes upon request.

Site preparation and installation are NOT included in unit cost.

TimberHomes Vermont | 21 Fork Road | Montpelier, VT 05602 Contact: info@timberhomesllc.com, (802) 685-7974 Made in Vermont by a Worker-Owned Company