

AGENCY OF TRANSPORTATION

FY 2026	Municipa	al Highway (Grant Application
APPLYING FOR	: 🗸 Structures	Class 2 Roadway	Emergency
MUNICIPALITY	: Richmond MU	NICIPAL CONTACT	(name): Peter Gosselin
MAILING ADDRE	SS: 203 Bridge Street, R	ichmond VT 05477	
Phone: (802) 434	I-2631 E-M	[ail: pgosselin@richmo	ndvt.gov
ACCOUNTING SY	YSTEM: 🗸 Autom	ated Manual	Combination
SAM #: 01933699	99 Gra	nntee FY End Month (m	nm format): 06
DISTRICT CONT	ΓΑCT (name): Jim Cot	a	
Phone: 655-1580	وبين والمراوي من وأراب والمنافق والمراوي والمنافق والمنافق والمنافق والمراو والمراوي والمراوي والمراوي والمراوي	Mail: jim.cota@vermon	ıt.gov
	K TO BE PERFORMI		
TH# <u>14</u> , (Name) Bridge #, Culvert # <u>1410</u> , for	Stage Road which crosses	which is a cla	wing town highway / structure: ass 3 town highway. e replacement size is 142"x91"x60'
Causeway:			
Retaining Wall:		. 1 70 FF F0	MACACA STATE
Latitude: 44.33.27	Longi	tude: 72.55.58	MM (If Available):
Guardrails are tipp and showing signs	oing out from the road du	e to lack of adequate sh topped from the July 16	study concludes the culvert is undersized noulder. The center of the culvert is bowed 3, 2023 storm and washed out 2650 feet of 2024 storm.
Reason For Probl	lem:		
Aged and undersize	ed drainage crossing cul	vert.	
			rrugated metal arch pipe with poured in
See attached	timate (below or atta	ched):	
Estimated Project	Amount: \$ 486,277.00	Estimated	Completion Date: 11/15/2026

Municipality has adopted Codes & Standards that med Municipality has a current Network Inventory?	et or exceed the State approved template? YES NO		
Municipality MUST complete the following envi			
EXISTING STRUCTURES: (check all that app			
Steel Tube Culvert	Concrete Box Culvert		
Stone Culvert	Concrete Bridge		
Ditch	Rolled Beam/Plate Girder Bridge		
Metal Truss Bridge	Wooden Covered Bridge		
There are foundation remains, mill ruins, stone walls or other	Masonry Structure		
Stone Abutments or Piers	Buildings (over 50 yrs old) within 300 feet of work		
Other:			
PROJECT DESCRIPTION: (check all that appl	у)		
The project involves engineering / planning only	The project consists of repaving existing paved surfaces only		
The project consists of reestablishing existing ditches only within existing footprint	All work will be done from the existing road or shoulder		
The structure is being replaced on existing location / alignment	There will be excavation within 300 feet of a river or stream		
New structure on new alignment	Repair/Rehab of existing structure		
There will be excavation within a flood plain	Road reclaiming, reconstruction, or widening		
Tree cutting / clearing	Temporary off-road access is required		
New ditches will be established	The roadway will be realigned		
The municipality has included photos of the project features as much as possible. YES			
Below this line to be filled in by VTrans staff: Recommended Award Amount:			
District Staff Approval: (name)	Date:		

Estimated project cost summary:

Construction signage and traffic control devices Excavation Guardrails remove and replace (150 lf) Culvert 142" x 91" x 60' arch pipe Culvert bands Retention sills Freight for new culvert Iump sum 1000 200' @ \$40 800 60' @ \$650 3900 2 x @ \$1100 220 11 x @ \$1150 1260 Iump sum 250	00
Excavation all site work 150,00 Guardrails remove and replace (150 lf) 200' @ \$40 800 Culvert 142" x 91" x 60' arch pipe 60' @ \$650 3900 Culvert bands 2 x @ \$1100 220 Retention sills 11 x @ \$1150 1260	00
Culvert 142" x 91" x 60' arch pipe 60' @ \$650 3900 Culvert bands 2 x @ \$1100 220 Retention sills 11 x @ \$1150 1265	00
Culvert 142" x 91" x 60' arch pipe 60' @ \$650 3900 Culvert bands 2 x @ \$1100 220 Retention sills 11 x @ \$1150 1265	00
Retention sills 11 x @ \$1150 1265	00
——————————————————————————————————————	00
Freight for new culvert lump sum 250	50
a resource recovered and results and resul	00
Drainage stone 200 ton @ \$40 800	00
Type III stone 50 ton @ \$30 150	00
Bank run gravel 200 ton @ \$20 400	00
Plant mix gravel 150 ton @ \$40 600	00
Road fabric LS 100	00
Jersey barriers lump sum 15,00	00
Trucking 40 hours @ \$200 800	00
Job site illumination lump sum 500	00
Inlet headwall (concrete) lump sum 4000	00
Outlet headwall (concrete) lump sum 4000	00
Topsoil seed and mulch lump sum 500	00
Engineering, easements and plans lump sum 5500	00
Subtotal \$422,85	50
Project 15% contingency <u>6342</u>	27
Total project estimated cost \$486,27	77

Maximum allowable project state grant funding \$200,000 Town bridge and culvert reserve (20% match plus project balance) \$286,277

submitted by: Peter Gosselin 4-4-25



March 23, 2018

Town of Richmond Attn: Pete Gosselin, Road Foreman 203 Bridge Street Richmond, VT 05477

RE: Hydraulic Study - Stage Road (TH14)

GPS Coordinates: 44.39374 N / -72.93248W

Waterbody: Unnamed tributary to the Winooski River

Project Understanding

East Engineering has completed a preliminary hydraulic study for the above referenced site and has summarized details of the study in subsequent sections of this letter. A site visit was conducted on March 21, 2018 to visually inspect the stream, road, and culvert conditions. Due to heavy snowpack and ice conditions, approximate measurements were completed for the road, stream, and culvert. Measurements should be refined/confirmed, and this study revised (if necessary), once the site clears of snow/ice.

Hydrology

This site consists of a hilly/mountainous drainage basin, is primarily wooded with steep grades, and is located in a rural setting. Near the road crossing, the stream channel slope averages approximately 7%, however, there is a mix of areas that have plunges (steeper than 7%) and sections that meander (shallower than 7%). The area immediately upstream and downstream of the culvert (approximately 50' either direction) have a channel slope of approximately 2-4%. The total drainage area upstream of the culvert inlet is approximately 0.95 mi².


The following design flow rates were obtained from USGS StreamStats:

Recurrence Interval (Years)	Flow Rate in Cubic Feet Per Second (CFS)
Q2	53
Q10	114
Q25	154 (Local Road Design)
Q50	190
Q100	229 (Check Flow)



Channel Morphology


This stream channel is steep and consists of large boulders, ledge outcroppings and plunge pools. Both inlet and outlet banks are steep and wooded. The bank full width varies and ranges from 8-12 feet, with several larger pool areas (depending on boulder/ledge locations) and several narrow channel locations. The depth of the stream varies and is shallow at some of the drops and has several pools that are several feet deep. The culvert inlet sits in a topographic



depression, which has collected debris during higher flow events. The outlet channel appears to be slightly scoured due to higher velocities caused by the undersized culvert. The outlet channel generally parallels Stage Road in the vicinity of the project.

Existing Conditions

The existing structure is a 5' diameter corrugated metal pipe culvert, which is both galvanized and tar coated, providing approximately 20 ft² of waterway opening. The top half of the culvert appears to be in fair condition, given the age, however, the bottom portion of the culvert has lost all galvanized and tar coatings and shows signs of corrosion and deterioration. The inlet headwall of the culvert is stacked stone, which is in poor condition and is deteriorating. Due to the grade difference between



the road and the stream, both the inlet and outlet slopes above the headwalls are very steep and show signs of erosion.

The structure is not in compliance with the VTrans Hydraulic Manual, does not meet bankfull width requirements, and restricts aquatic organism passage (AOP). Hydraulic calculations for the existing culvert were completed using HY-8 Culvert Hydraulic Analysis Program, published by the US Department of Transportation, Federal Highway



Administration. Results show that headwater depths do not overtop the roadway, however, are not in accordance with the VTrans Hydraulic Manual. Headwater depths of 5.7' at Q100 and 4.2' at Q25 were calculated.

Replacement Recommendations

The span, geometry, and installation method of the replacement structure should meet several criteria, including:

- Vermont Stream Alteration General Permit
- VTrans Hydraulic Manual Standards

Based on the preliminary sizing information, the following structures should be considered. Minimum requirements include a 11' clear span and 44 ft² of waterway opening. The structure criteria should be further evaluated during final design to ensure compatibility with site conditions.

- 1. Metal Pipe Arch (Galvanized Steel or Aluminum): Exact structure dimensions vary by manufacturer, however, a structure with approximate dimensions of 11'-8"x5'-9" will provide the required waterway opening and minimum span. Pipe arches are manufactured with both closed bottoms and open bottoms. Open bottom is preferred, however, if a closed bottom is utilized, sills should be spaced at 8' increments and be "V" shaped (12" at sides, 8" in middle). Natural stream gravel or a clean (no fines) cobble/stone product should be added between sills. Concrete footers/pedestals/headwalls will be required to complete the structure installation. This structure will result in headwater depths of approximately 3.3' at Q25 and 4.8' at Q100 with no roadway overtopping.
- 2. Precast Concrete Box Culvert: The structure should have an 11' span and 6' high (inside opening). The box invert should be buried approximately 2' below natural stream channel elevations, which would result in an opening of 11'x4' (44 ft²). The box culvert should have sills spaced at 8' intervals and be "V" shaped (12" at sides, 8" in middle). The precast concrete box will require headwalls, wingwalls, and cutoff walls for a complete installation. This structure will result in headwater depths of approximately 2.5' at Q25 and 3.4' at Q100.
- 3. Any similar structure that meets the minimum requirements of this analysis and the site conditions.

General Comments

Regardless of the selected replacement structure, several common items should be implemented.

1. If a closed structure (4-sided concrete box, or pipe arch) are used, the inverts should be buried to a level of 2' below natural channel elevation.



- 2. The wingwalls and cutoff walls should extend 4' below the invert of the streambed, or to ledge, to prevent undermining of the structure.
- 3. Wingwalls should be used to transition from the road grade to the stream banks. Properly sized wingwalls will mitigate road bank erosion issues and also provide additional protection from stream undermining/scouring.
- 4. Type III stone should be used to armor/anchor the transition from the wingwalls to the surrounding ground and for the culvert inlet/outlet.
- 5. Both US Army Corps of Engineers and Vermont Agency of Natural Resources
 Stream Alteration should be contacted during the design phase to ensure
 the proposed project complies with applicable permitting standards.
- Metal pipe arches have specific requirements regarding backfill and cover between top of structure and roadway elevation. The site should be able to provide adequate cover; however, this should be evaluated during final design.
- 7. As previously noted, due to snowpack/ice, approximate dimensions were obtained for the hydraulic calculations. Prior to final design, field dimensions should be confirmed, and design flows calibrated.

Please let me know if there are any questions or you need any additional information.

Sincerely,

Tyler Billingsley, P.E. Engineer / Owner